CYCLE LOCKER

Asgard
storage for life

BASE INSTRUCTIONS
Flat and firm base. Recommended: concrete, tarmac or paving flags.
Min. distance from walls/ shrubbery: 1000mm.
Min. base size (WxDxH) 1100mm x 2250mm x 50mm.

LEVELING THE UNIT
Correctly level the constructed unit using the shims (ZCOMPPLAS) provided prior to fixing the unit to the ground. Slide the packing pieces under the corners of the unit base as required until an equal gap has been achieved around the door allowing for its smooth operation and alignment.

It is always recommended to anchor the unit to the ground. Drill through the four holes in the base rails of the unit using 6mm dia masonry drill to a depth of 70mm. Screw in the anchor fixings. (These have a self cutting thread). **If not anchoring the unit, fit the 4 self-seal plugs BEFORE BUILDING to block the fixing holes underneath to stop water from entering the unit.**

TOOLS REQUIRED
Power driver POSI-DRIV screwdriver, 6mm dia. masonry drill and a 8mm and 10mm socket or spanner.

⚠ Warning: some panels may weigh over 20Kg. Beware of manual handling

TOP PANEL 63838 x1

LH SIDE PANEL 63854 x1

BACK PANEL 63706 x1

ROOF STIFFENER 63852 x2

BASE 63695 x1

RH SIDE PANEL 63855 x1

DOOR PANEL 63845 x1

FRONT STIFFENER 63991 x1

SEALANT ZSILCO1 x1

ZSCREW32 x4

ZCOMPPLZS02 x4

ZCOMPPLAS22-23-24 x6
2x 2mm, 2x 3mm, 2x 5mm

L BRACKET 63990 x4

ZHWNUT41 X12

ZSCREW100 x105

ZSCREW340 x21

YOUR UNIQUE KEY CODE

Warning: Please keep this key card safe! Refer to if replacement key is required.

Posi-Driv Screwdriver

6mm Dia.

8mm & 10mm Spanner

18V

x2

PLEASE NOTE ALL SCREWS ARE FIXED FROM THE INSIDE

1 LAY THE BASE IN POSITION
& SILICONE THE FOUR CORNERS
HIGHLIGHTED BELOW

FRONT OF BASE

BASE 63695

2 ALIGN & SCREW IN SIDE PANEL.
SILICONE INSIDE THE SIDE PANEL
CORNERS

LH SIDE PANEL 63854

x15

3 ALIGN & SCREW IN SIDE PANEL.
SILICONE INSIDE THE SIDE PANEL
CORNERS

RH SIDE PANEL 63855

x15

4 SCREW IN BACK
PANEL

BACK PANEL 63706

x15

5 UNFOLD TABS ON BOTH
SIDE PANELS

6 PLACE FRONT STIFFENER.
NO SCREWS REQUIRED AT
THIS TIME.

FRONT STIFFENER 63991

7 ROTATE TOP TO ACHIEVE DESIRED SLOPE. PLACE AND SCREW IN

TOP PANEL 63838

x23

8 POSITION THE ROOF STIFFENERS ALIGNING THE SLOPE WITH THE ROOF. SCREW IN

ROOF STIFFENER 63852

x4

9 FASTEN 4x L SHAPE BRACKETS TO INSIDE OF DOOR FRAME. INSERT SCREWS IN FRONT & FASTEN NUT FROM INSIDE.

x12

x12

L BRACKET 63990

10 INSERT 4 ZSCREW100s FROM INSIDE THE SHED. THROUGH THE FRONT STIFFENER AND TAB, AND INTO THE ROOF.

x4

11 SECURE THE DOOR

x9

12 LEVEL SHED UNTIL DOORS ALIGN USING ZCOMPPLAS AS SUITABLE

13 BOLT DOWN
THE LOCKER

x4